

Bill # 2

Concrete Works

Item	Description	Quantity	Unit	Unit rate	Amount.
1	CONCRETE 50 mm thick bed of plain concrete class "C" with ordinary Portland Cement in blinding under reinforced concrete columns bases, footing of walls and site beams .	22	cbm	\$ 130	\$2,860
2	200 mm thick reinforced concrete class "A" (Slab on grade) <u>Vibrated Reinforced Concrete Class "A" with Ordinary Portland cement , Well Punned Around Steel Reinforcement Rods and Bars and Between Formwork and Including Formwork (Steel Reinforcement Rods and Bars Measured Separately) as Shown on Structural Drawings and as Specified:</u>	82	cbm	\$ 210	\$17,220
3	Columns bases, footings of walls and tie tems, Ceiling.	459	cbm	\$ 220	\$100,980
4	Columns and walls .	210	cbm	\$ 220	\$46,200
5	Haunches and walls of water tanks with approved waterproofing additive and P.V.C water stops .				
6	Parapets	91 19	mr cbm	\$ 45 \$ 150	\$4,095 \$2,850
7	Curbs	103 10	mr cbm	\$ 12 \$ 150	\$1,236 \$1,500
8	Door and window lintels , jambs and sills and including steel reinforcement rods and stirrups .	160 4	mr cbm	\$ 12 \$ 150	\$1,920 \$600
9	Drop beams	70 7	mr cbm	\$ 22 \$ 150	\$1,540 \$1,050
10	100 mm thick attic solid base slabs , and including deformed reinforcement rods according to working drawings or to notes ordered by the Engineer. Above 1 bathroom/ Apart	4	cbm	\$ 200	\$800
Grand total of bill # 2					\$182,851