

BILL # 3**Block work and Brick work**

Item	Description	Quantity	Unit	Unit rate	Amount.
	<u>PREAMBLE</u> Precast Hollow Concrete Blocks Of Standard Size, Bedded and Jointed in Ordinary Portland Cement and Salt Free Sand (1:3) Mix with placing of wire mesh in between block rows (every other row) and placing of angle bids and planting 6 mm steel bars in all concrete and masonry wall connections.				
1	100 mm thick Solid blockwalling .				
2	100 mm thick blockwalling .	2486	sqm	12.5	\$31,075
3	150 mm thick blockwalling .	170	sqm	18	\$3,060
4	Thermal / Sound insulation - Density 70	742	sqm	6	\$4,452
	Grand total of bill # 3				\$38,587