

BILL # 7**Plaster Works**

Item	Description	Quantity	Unit	Unit rate	Amount.
	<u>INTERNAL PLASTER</u>				
	<u>Prepare Surfaces , Spatterdash and Render in Ordinary Portland Cement and Float Finish Coat with 200 kgs Cement and 200 kgs Slaked lime per Meter Cube of Sand as Specified to Surface of :</u>				
1	Walls , sides of columns	2929	sqm	\$ 10	\$ 29,290
2	Ceilings , sides and soffit of beams	833	sqm	\$ 10	\$ 8,330
3	Bathrooms	462	sqm	\$ 12	\$ 5,544
	<u>EXTERNAL PLASTER</u>				
1	Prepare surfaces , spatterdash , render and float in ordinary Portland Cement and salt free sand as specified to surfaces and top face of roof parapets facing roof deck to receive waterproof paint (Scaffolding included)	1150	sqm	\$ 17	\$ 19,550
2	Ditto but parapets facing balconies (ditto)	98	sqm	\$ 13	\$ 1,274
	Grand total of bill # 7				\$63,988